LIGHTING IS SHOWN FOR INDICATIVE PLACEMENT ONLY. CONFIRM THE LIGHTING LEVELS WITH THE LIGHTING ENGINEER.

INTERIOR LIGHT LEGEND

LT-1A	DOWNLIGHT, REFLECTOR ANGLE 15º
LT-1B	DOWNLIGHT, REFLECTOR ANGLE 40º
LT-1C	DOWNLIGHT, REFLECTOR ANGLE 60º
LT-1D	POWER TRACK MOUNTED SPOTLIGHTS
LT-2A	SUSPENEDED LIGHT FRAME RGB LED
LT-2B	SUSPENEDED LIGHT PANEL RGB LED
LT-3	DOWNLIGHT LOW CEILING
LT-4	WALL FLOODLIGHT FOR THE WELCOME WALL
LT-5	CEILING MOUNTED LIGHT FRAME RGB LED
LT-6	LIGHT CHANNEL, SUSPENDED GENERAL
LT-7	LIGHT CHANNEL, SUSPENDED NVD AND BOARDROOM
LT-8	LIGHT CHANNEL, WALL MOUNTED PUBLIC WASHROOMS
LT-9	LED HIGH BAY FIXTURE
LT-10A	FLUORESCENT WRAP AROUND
LT-10B	FLUORESCENT WASH BAY
LT-11A	FLUORESCENT STRIP LIGHT C/W WIRE MESH PARTS
LT-11B	FLUORESCENT FIXTURE - SHOP WATER PROOF
LT-12	SQUARE POT LIGHTS
LT-13	VESTIBULE
LT-17	UNDER CABINET LED STRIP

EXTERIOR LIGHT LEGEND / OUTLETS

ELT-1	LOT LIGHTING
ELT-2	WALL PACK LIGHTS
ELT-3	BOLLARD LIGHTS
	SHOWROOM FLOOR OUTLET

NOTES:

- THIS LEGEND IS TO BE READ IN CONJUNCTION WITH LIGHTING SCHEDULE.
- PLEASE PROVIDE AT LEAST ONE IN FLOOR POWER BOX UNDER EACH WORK STATION AND UNDER EACH VEHICLE.
- PROVIDE PHOTOMETRIC CALCULATIONS CONFIRMING SHOWROOM LIGHTING LEVELS. LIGHTING TO MEET MINIMUM 500 LUX STANDARDS AS NOTED ON PAGE 50 OF DCD.

CEILING FINISH LEGEND

C1 - 2'x4' ACOUSTIC TILE CEILING WHITE	C2 - GYPSUM BOARD CEILING PAINTED DARK GREY
C3 - GYPSUM BOARD CEILING PAINTED WHITE	C4 - EXPOSED STRUCTURE PAINTED WHITE

Note:
1. All dimensions and conditions must be verified on site.
2. Reproduction of this drawing is not permitted without the written authorization of EVEREST ENGINEERING LIMITED.
3. Drawings are not to be used for construction or pricing unless signed by the Engineer and labelled "ISSUED FOR CONSTRUCTION"

LEGEND

	DUPLEX RECEPTACLE
	DUPLEX RECEPTACLE., SEPERATE CIRCUIT
	SPLIT DUPLEX RECEPTACLE
	SPECIAL RECEPTACLE SIZE AS NOTED
	DIRECT CONNECTION
	DUPLEX RECEPTACLE C/W TOP SWITCHED
	DUPLEX RECEPTACLE ISOLATED GROUND
	RECESSED FLOOR & DATA OUTLET
F/R	FIRE RATED RECESSED FLR & DATA OUTLET
	FLUORESCENT LIGHT, CEILING MOUNTED
	FLUORESCENT LIGHT, WALL MOUNTED
	INCANDESCENT CEILING LIGHT FIXTURE
	WALL MOUNTED LIGHT FIXTURE
	SINGLE PHASE MOTOR CONNECTION
	THREE PHASE MOTOR CONNECTION
$	SINGLE POLE LIGHT SWITCH
$3	3 WAY LIGHT SWITCH
$4	4 WAY LIGHT SWITCH
	FUSIBLE DISCONNECT SWITCH
	UNFUSED DISCONNECT SWITCH
	ELECTRICAL BREAKER PANEL
	TELEPHONE OUTLET
	TELEPHONE AND DATA OUTLET
	EMERGENCY BATT. PACK W/2 HEADS
	REMOTE EMERGENCY LIGHT HEAD
	EXIT FIXTURE CEILING MOUNTED
	EXIT FIXTURE WALL MOUNTED
U/G	UNDERGROUND
W.P.	WEATHER PROOF
R	END OF LINE RESISTOR
T	TELEPHONE PULL BOX SIZE AS NOTED
C	CABLE TV. PULL BOX SIZE AS NOTED
HP	HYDRO POLE
	ELECTRIC FAN FORCED HEATER
	BASEBOARD HEATER
	MAGNETIC MOTOR STARTER

NO.	REVISION/ISSUE	DATE
4	REVISED TO MATCH ARCHITECT	MAR 25/25
3	ISSUED FOR PRICING	OCT 11/24
1	ISSUED FOR BUILDING PERMIT	OCT. 18/23
0	PRELIMARY REVIEW	APRIL 2023

NORTH

STAMP
REGISTERED PROFESSIONAL ENGINEER
G. LASCHEWSKI
PROVINCE OF ONTARIO

EVEREST ENGINEERING LIMITED
15 Bass Road, Lombardy, Ontario K0G 1L0
(613) 831-5454 everestengineering@bellnet.ca
MECHANICAL & ELECTRICAL ENGINEERS

PROJECT
Bytek Volkswagen
1325 St Laurent Blvd,
Renovation
OTTAWA — ONTARIO

SCALE 1:100	DRAWN BY C.V.A.
ISSUED	CHECKED BY G.L.
DATE MARCH 2023	PROJECT NO.

DRAWING NUMBER E—1 OF 4 | REV. NO.

TITLE
BASEMENT PLAN